




PHOTOGRAPH OF EXISTING MONITORING BOREHOLE



PHOTOGRAPH OF EXISTING MANHOLE SHOWING LEACHATE DRAIN

- LEGEND**
- 8.0 ——— EXISTING CONTOURS m AOD
 - EXTENT OF PROPOSED RESTORATION WORKS. (Approx 8 HECTARES)
 - EXISTING FENCELINE
 - BH 15A EXISTING SITE MONITORING BOREHOLES
 - LMC 1 EXISTING LEACHATE MONITORING CHIMNEY
 - EXISTING SITE DRAINAGE INFRASTRUCTURE
 - MH6 EXISTING MANHOLES
 - EXISTING TRAMMEL DRAIN
 - EXISTING TREE CANOPY

- NOTES**
- 1 THIS DRAWING SHALL BE READ IN CONJUNCTION WITH:
 - MWDA.530-101-001 EXISTING SITE LAYOUT AND INFRASTRUCTURE
 - MWDA.530-101-002 PROPOSED FINAL CONTOURS
 - MWDA.530-101-003 PROPOSED PHASING OF WORKS
 - MWDA.530-101-004 PROTECTION TO EXISTING INFRASTRUCTURE
 - 2 ALL DIMENSIONS IN METRES
 - 3 ALL CONTOURS IN METRES TO AOD
 - 4 EXISTING SITE CONTOURS TAKEN AS SURVEYED 1998
 - 5 THE EXTENT OF RE-PROFILING, AS INDICATED, SHALL RUN AS FAR AS THE BASE OF THE EXISTING MONITORING BOREHOLES ONLY.
 - 6 WORKS TO BE COMPLETED IN PHASES AS INDICATED, OR IN ACCORDANCE WITH ALTERNATIVE AGREED PLAN
 - 7 EXISTING INFRASTRUCTURE TO BE SUFFICIENTLY PROTECTED DURING WORKS TO ENABLE REINSTATEMENT BY OTHERS FOLLOWING COMPLETION OF EACH PHASE OF RESTORATION WORKS
 - 8 ACCESS TO SITE SHALL BE MADE VIA THE EXISTING DROPPED KERB IN THE NORTH WEST CORNER OF THE SITE. EXISTING PAVEMENT AND SERVICES SHALL BE SUITABLY PROTECTED



ACCESS ONTO SITE SHALL BE MADE FROM FOUL LANE VIA EXISTING DROPPED KERB
Scale 1:250

Reproduced from Ordnance Survey Mapping with the permission of the controller of Her Majesty's Stationery Office © Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Merseyside Waste Disposal Authority LA07635X

Rev.	Amendment	Date
Site		
FOUL LANE FORMER LANDFILL SITE		
Title		
RESTORATION WORKS EXISTING SITE GENERAL ARRANGEMENT AND INFRASTRUCTURE		
Merseyside Recycling & Waste Authority 1st Floor No 1 Mann Island Liverpool L3 1BP		
A1	Drg. No. MWDA.530-101-001	Rev.
 Scale 1:1000		
Drawn	ASB	Date JULY 2016