



— PROPOSED GROUND PROFILE
 — EXISTING GROUND PROFILE



LEGEND	
8.0	EXISTING CONTOURS
10	PROPOSED CONTOURS
(Green dashed line)	EXTENT OF PROPOSED RESTORATION WORKS
(Black dashed line)	EXISTING FENCELINE
(Black dot)	EXISTING SITE MONITORING BOREHOLES
(Hatched area)	EXISTING SITE DRAINAGE INFRASTRUCTURE
(Green wavy line)	EXISTING TREE CANOPY



- NOTES**
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH:
 - MWDA.530-101-001 EXISTING SITE LAYOUT AND INFRASTRUCTURE
 - MWDA.530-101-002 PROPOSED FINAL CONTOURS
 - MWDA.530-101-003 PROPOSED PHASING OF WORKS
 - MWDA.530-101-004 PROTECTION TO EXISTING INFRASTRUCTURE
 - ALL DIMENSIONS IN METRES
 - ALL CONTOURS IN METRES TO AOD
 - EXISTING SITE CONTOURS TAKEN AS SURVEYED 1998
 - THE EXTENT OF RE-PROFILING, AS INDICATED, SHALL RUN AS FAR AS THE BASE OF THE EXISTING MONITORING BOREHOLES ONLY.
 - BERMS SHALL BE FORMED ON THE SIDE SLOPES TO PREVENT SOIL EROSION PRIOR TO ESTABLISHMENT OF VEGETATION
 - IN PROFILING THE SIDE SLOPES, PROVISION SHALL BE MADE FOR 4 WHEEL DRIVE VEHICULAR ACCESS AROUND THE PERIMETER OF THE SITE, AND AGRICULTURAL TYPE VEHICULAR ACCESS ACROSS THE SITE AS A WHOLE
 - WORKS TO BE COMPLETED IN PHASES AS INDICATED, OR IN ACCORDANCE WITH ALTERNATIVE AGREED PLAN
 - EXISTING INFRASTRUCTURE TO BE SUFFICIENTLY PROTECTED DURING WORKS TO ENABLE REINSTATEMENT BY OTHERS FOLLOWING COMPLETION OF EACH PHASE OF RESTORATION WORKS

Rev.	Amendment	Date

Site
FOUL LANE FORMER LANDFILL SITE

Title
**RESTORATION WORKS
 PROPOSED RESTORATION PROFILE**

MWDA Merseyside Recycling & Waste Authority
 1st Floor
 No. 1 Mann Island
 Liverpool
 L3 1BP

A1 Drg. No. **MWDA.530-101-002** Rev. .

Scale 1:500

Scale 1:1000
 Scale 1:500
 Date July 2016

Reproduced from Ordnance Survey Mapping with the permission of the controller of Her Majesty's Stationery Office. Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Merseyside Waste Disposal Authority L407635X